

INDIAN REGISTER OF SHIPPING

CLASSIFICATION NOTES

Fuel Oil Treatment System

September 2018



IRCLASS
Indian Register of Shipping

CLASSIFICATION NOTES

Fuel Oil Treatment System

September 2018

Contents

Section

- 1 Introduction
- 2 Treatment of Fuel Oil on Board Ships
- 3 Test Procedures to confirm the ability of RMF fuel oil pumps operation with marine fuels with low viscosity

Section 1

Introduction

1.1. Background

1.1.1 This Classification note provides the requirements for Fuel Oil Treatment System in order to help improve the operational safety of the vessel by increasing the reliability of the oil fuelled machinery.

1.1.2 This document recognizes that there is a disparity between the quality of fuel bunkered and delivered in accordance with ISO 8217: 2017, and the fuel quality requirements typically specified by marine diesel engine manufacturers. The performance of the system and equipment contained in fuel oil treatment system is fundamental to reducing the level of contaminants to within the oil fuelled machinery manufacturers specifications.

1.1.3 It is recommended that, MEPC.1/Circ.875 “*Guidance on best practice for fuel oil purchasers/users for assuring the quality of fuel oil used on board ships*” may be followed to assist in assuring the quality of fuel delivered to, and used on board ships.

1.2 Class Notation

1.2.1 Vessels with fuel oil treatment system and equipment complying with the relevant requirements of this Classification Note will be assigned an additional class notation **FT (___ to ___ cSt, ___ to ___ kg/m³)**. The numbers in brackets indicate the following :

- (a) Minimum value to Maximum value of viscosity [cSt] at 50°C; and
- (b) Minimum value to Maximum value of density [kg/m³] at 15°C of the fuel oil

Section 2

Treatment of Fuel Oil on Board Ships

2.1 Application

2.1.1 The following requirements apply to fuel treatment systems for oil fueled machinery on board ships. The requirements cover the complete fuel oil treatment system, from the fuel bunker connection through to the interface with the oil fueled machinery; this includes fuel tanks, the fuel cleaning equipment and the fuel conditioning equipment.

2.2 Definitions

2.2.1 A **service tank** is a fuel oil tank, which contains only fuel of a quality ready for use, i.e. fuel of a grade and quality that meet the specification required by the equipment manufacturer.

2.2.2 **Fuel oil** means petroleum fuels for use in marine diesel engines.

2.2.3 **Fuel oil treatment system** means a system intended for:

- Cleaning of the fuel oil by removal of water, catalyst fines, water bound ash constituents (e.g. sodium) and particulate matter,
- Conditioning of the fuel oil to ensure efficient combustion.

2.2.4 **Oil fueled machinery** means all machinery combusting fuel oil, including main and auxiliary engines, boilers, gas turbines.

2.3 System Level Requirements

2.3.1 Functional Requirements

2.3.1.1 The fuel oil treatment system is to reduce the level of contaminants and condition the fuel such that it ensures the fuel is ready for use by the oil-fueled machinery and there is no detrimental effect on the reliability and safety of such machinery.

2.3.2 Performance requirements

2.3.2.1 The capacity and arrangements of the fuel oil treatment system is to be suitable for ensuring availability of treated fuel oil for the Maximum Continuous Rating (MCR) of the propulsion plant and normal operating load at sea of the generator plant.

2.3.2.2 The capacity and arrangements of the fuel oil treatment system is to be determined on the basis of the requirements of the oil fueled machinery manufacturer and the types of fuel: Residual Marine Fuel (RMF), Distillate Marine Fuel (DMF) to be bunkered to the ship.

2.3.2.3 The fuel oil treatment system is to be provided with redundancy so that failure of one system will not render the other system(s) inoperative. Arrangements are to be made to ensure that any single failure in the system will not interrupt the supply of clean fuel to machinery used for propulsion and electrical generating purposes where the fuel conditioning system is installed between fuel oil service tanks and the inlet to the combustion system.

2.3.2.4 Main bunker tanks are to be arranged to limit the need to mix newly bunkered fuel with fuel already on-board as far as practicable. When mixing of fuel oil is necessary, a compatibility test is to be performed, prior to transfer.

2.3.2.5 The fuel oil at engine inlet is to be of properties recommended by the engine manufacturer.

2.3.2.6 The maximum amount of water reaching the engine is to be 0.3 % v/v or according to engine maker's recommendations.

2.3.2.7 The maximum amount of catalyst fines reaching the engine is to be 10 ppm Al+Si and in some instances this might rise to 15 ppm. However every attempt must be made to reduce the catalyst to the lowest possible levels.

Note: Particle size has a significant influence on the capacity of the centrifugal separators to lower the level of catalyst fines in the fuel, with particles of 2 microns or less being particularly difficult to remove. The presence of particles of 2 microns size or lower may cause difficulties in achieving the 10 ppm limit. Engine manufacturer recommendations are also to be referred to for any further system specific recommendations.

2.4 System interfaces

2.4.1 Bunkered fuels are to meet the requirements of ISO 8217 (latest revision) or an oil fueled machinery manufacturers' specification.

2.4.2 Locations of sampling points

2.4.2.1 The fuel oil treatment system is to be provided with sampling points.

2.4.2.2 The sampling points are to meet the requirements of MEPC.1/Circ.864 '*Guidelines for on board sampling and verification of the sulphur content of the fuel oil used on board ships*' and are to be located as follows:

- .1 after the transfer pump discharge,
- .2 before and after the fuel cleaning equipment, and

.3 after the fuel oil service tank, before any fuel change over valve,

.4 before fuel enters the oil fuelled machinery.

2.4.2.3 Sampling points are to be provided at locations within the fuel oil system that enable samples of fuel oil to be taken in a safe manner.

2.4.2.4 The position of a sampling point is to be such that the sample of the fuel oil is representative of the fuel oil quality passing that location within the system.

2.4.2.5 The sampling points are to be located in positions as far removed as possible from any heated surface or electrical equipment so as to preclude impingement of fuel oil onto such surfaces on equipment under all operating conditions.

2.4.3 Verification requirements

2.4.3.1 Approval

2.4.3.1.1 Plans and documents demonstrating compliance with the requirements included in section 2.4.3 are to be submitted for consideration.

2.4.3.2 Shipboard verification

2.4.3.2.1 The fuel oil treatment system is to be inspected by the Surveyor after installation on board to confirm that the arrangement, installation and workmanship are in accordance with the equipment specification and the requirements of this classification note.

2.4.3.2.2 The fuel oil treatment system is to be provided with sampling cocks located in convenient positions e.g. at the transfer pump from the bunker tanks, before and after the centrifuges and after the service tank.

2.4.3.2.3 Diagram of sampling points showing sampling points location is to be retained on board the ship and is to be presented to the surveyor during regular surveys.

2.4.3.2.4 Records of fuel sample analysis according to the relevant revision ISO 8217 is to be retained on board the ship and should be presented to the surveyor during regular surveys.

2.4.3.2.5 It is recommended that a drip sample of fuel should be taken during bunkering at the bunker manifold in accordance with ISO 3170 or 3171 and ISO 13739, where applicable.

2.4.3.2.6 It is recommended that once a new bunker has started to be used, a fuel system audit is performed by a responsible person on board, taking fuel samples from before and after the treatment plant and at the engine fuel rail.

2.5 Equipment level requirements

2.5.1 Fuel tanks

2.5.1.1 Functional requirements

2.5.1.1.1 Settling and service tanks for fuel oil are to be designed and constructed in such a way as to direct water and sludge towards a drainage outlet.

2.5.1.1.2 If settling tanks are not provided, the fuel oil bunker (storage) and daily service tanks are to be designed and constructed in such a way as to direct water and sludge towards a drainage outlet.

2.5.1.2 Performance requirements

2.5.1.2.1 Fuel is to be maintained at a temperature commensurate with the needs of system equipment to function in accordance with manufacturers' requirements.

2.5.1.2.2 A temperature controller of PID type is to be fitted to ensure that the fuel is maintained at the temperature required for optimum system performance.

2.5.1.3 Equipment interfaces

2.5.1.3.1 Open drains for removing the water from fuel tanks are to be fitted with valves or cocks of the self-closing type.

2.5.1.3.2 A tank drain cock is not to be considered as a sampling point.

2.5.1.3.3 Fuel suction points are to be located at an appropriate distance above the tank drain point to prevent accumulated water and sludge being drawn into the fuel oil treatment system.

2.5.1.3.4 It is recommended that at least one low suction point and one high suction point be provided on the settling and service tank.

2.5.1.4 Equipment Operations

2.5.1.4.1 Provision is to be made for collecting the discharge from the fuel oil tank bottom drain valves. Appropriate access is to be provided for personnel to enable tank maintenance operations to be conducted safely.

2.5.1.5 Physical characteristics

2.5.1.5.1 Fuel settling tanks and Fuel service tank bottoms are to slope towards the drainage outlet.

2.5.1.5.2 The internal surfaces of the bottoms of heavy fuel oil settling tanks and daily service tanks are to be such that the passage of sludge to the lowest part of the tank is not restricted.

2.5.1.5.3 The materials and/or their surface treatment used for the storage and distribution of fuel oil are to be selected such that they do not introduce contamination or modify the properties of the fuel.

2.5.1.5.4 The Service tank overflow return line to the settling tank is to be drawn from near the bottom of the service tank to the top of the settling tank to ensure any accumulating sediment in the service tank bottom is minimized.

2.5.1.6 Verification requirements

2.5.1.6.1 Approval

.1 Plans and documents demonstrating compliance with the requirements of 2.5.1 are to be submitted for approval.

2.5.1.6.2 Factory acceptance testing

.1 The sampling device is to be one of the following types:

- a) manual valve-setting continuous-drip sampler; or
- b) time-proportional automatic sampler; or
- c) flow-proportional automatic sampler.

.2 The sampling device is to be as per recognized standards such as ISO 3170 or ASTM D 4057 or BS 3195.

2.5.2 Fuel temperature management equipment

2.5.2.1 Functional requirements

2.5.2.1.1 Heaters and coolers are to safely manage the temperature of fuel oil, commensurate with the needs of the system design from storage to combustion machinery fuel rail. Cold Filter Plugging points and Cloud Points as well as the pour point for DMF fuels need to be considered in light of the ship's intended operating area and ambient temperatures.

2.5.2.1.2 When the engines are using low viscosity DMF (~ 2.0 – 3.0 cSt at 40 °C) it is recommended to install a cooler to the Fuel oil return line to ensure that minimum fuel injection viscosity specified by the equipment manufacturers can be maintained.

2.5.2.1.3 Fuel heater control is to be able to respond quickly to sudden fuel flow changes to avoid overheating, for example, during the discharge cycles of the centrifugal separators.

2.5.2.1.4 The presence on board of spare heaters and coolers is to be considered.

2.5.2.2 Performance requirements

2.5.2.2.1 Where heating or cooling of the fuel oil is required for the efficient functioning of the fuel oil treatment system, a minimum of two heating or cooling units are to be provided. Each heating or cooling unit is to be of sufficient capacity to maintain the required temperature of the fuel oil for the required delivery flow rate.

2.5.2.2.2 Automatic viscosity controllers are to be maintained as the primary means to control required injection viscosity with manual temperature control being only a secondary back up options. This will ensure that the broadening range of fuel formulations to meet the lower sulphur limits for both inside and outside ECA-SOx operations is addressed smoothly and not overlooked by the crew.

2.5.2.3 Equipment interfaces

2.5.2.3.1 Heaters and coolers are to be located to avoid oil spray or oil leakages onto hot surfaces or other sources of ignition, or onto rotating machinery parts. Where necessary, shielding is to be provided.

2.5.2.3.2 Heaters and coolers are to be located to allow easy access for routine maintenance.

2.5.2.4 Verification requirements

2.5.2.4.1 Approval

.1 Plans and documents demonstrating compliance with the requirements of 2.5.2 is to be submitted for approval.

2.5.2.4.2 Factory acceptance testing

.1 Heaters and coolers are to be manufactured under IRS survey. As an alternative, heaters and coolers may be manufactured and tested under an Alternative Certification Scheme, see *Pt.1 Ch.1, Sec 4 of Rules and Regulations for the Construction and Classification of Steel Ships*.

2.5.2.4.3 Shipboard verification

.1 Satisfactory heater or cooler operation is to be verified by Surveyor after installation on board.

2.5.3 Pumps

2.5.3.1 Functional requirements

2.5.3.1.1 Fuel pumps are to be capable of pumping all grades of fuel expected within the section of fuel system to which they are fitted.

2.5.3.2 Performance requirements

2.5.3.2.1 Fuel pump capacity is to ensure that fuel flow rate through the fuel system is sufficient to maintain the installed oil-fuelled machinery's fuel consumption during normal operation, according to SOLAS Regulation II-1/26.3.

2.5.3.3 Equipment interfaces

2.5.3.3.1 Fuel pumps are to be protected from coarse and abrasive solids entering the pump. The degree to which such solids are filtered is to be in accordance with the pump manufacturer's instructions.

2.5.3.3.2 Pumps are to be located to allow easy access for routine inspection and maintenance.

2.5.3.4 Verification requirements

2.5.3.4.1 Approval

.1 Plans and documents demonstrating compliance with the requirements of 2.5.3 are to be submitted for approval.

2.5.3.4.2 Factory acceptance testing

.1 Fuel pumps are to be manufactured under IRS survey. As an alternative, pumps may be manufactured and tested under an Alternative Certification Scheme, see *Pt.1 Ch.1, Sec 4 of Rules and Regulations for the Construction and Classification of Steel Ships*.

2.5.3.4.3 Shipboard verification

.1 Satisfactory fuel pump operation is to be verified by Surveyor after installation on board.

2.5.4 Filters

2.5.4.1 Functional requirements

2.5.4.1.1 Fuel filters are to reduce the level of contaminants in the fuel in order to minimize wear or other damage to functional elements of the fuel system e.g. pumps and oil fueled machinery.

2.5.4.2 Performance requirements

2.5.4.2.1 Fuel filters are to reduce the level of contaminants in the fuel to a level commensurate with the downstream equipment manufacturers' requirements.

2.5.4.3 Equipment interfaces

2.5.4.3.1 Filters are to be located to avoid oil spray or oil leakages onto hot surfaces or other sources of ignition, or onto rotating machinery parts. Where necessary, shielding is to be provided.

2.5.4.3.2 Filters are to be located to allow easy access for routine maintenance.

2.5.4.3.3 The arrangements of filters are to be such that any unit can be cleaned without interrupting the supply of filtered oil to the combustion system.

2.5.4.3.4 The design of filter and strainer arrangements is to be such as to avoid the possibility of them being opened inadvertently when under pressure.

2.5.4.4 Equipment Operations

2.5.4.4.1 The design and construction of fuel filters is to facilitate their safe maintenance and replacement of filter elements.

2.5.4.5 Physical characteristics

2.5.4.5.1 Filters are to be fitted in the fuel oil supply lines to each oil engine and gas turbine to ensure that only suitably filtered oil is fed to the combustion system.

2.5.4.6 Verification requirements

2.5.4.6.1 Factory acceptance testing

.1 The manufacturer is to verify and document that each fuel filter meets the declared performance specifications.

2.5.4.6.2 Shipboard verification

.1 Maintenance records for fuel oil filters are to be made available to the surveyor during regular ship surveys.

.2 Documentation is to be available to the surveyor which demonstrates that the correct fuel oil filter cleaning procedures and prescribed associated equipment is available.

2.5.5 Centrifugal Separators

2.5.5.1 Functional requirements

2.5.5.1 Where necessary to ensure reliable operation of main propulsion machinery and all auxiliary machinery essential to the propulsion and the safety of the ship, centrifugal separators are to remove water and particulates that would otherwise cause excessive wear or other related failures of the oil fuelled machinery.

2.5.5.2 Performance requirements

2.5.5.2.1 The total installed capacity of centrifugal separators is to be determined as part of the overall system design in order to achieve the oil fuelled machinery manufacturers requirements for fuel quality. However, a minimum of two separators, each of a capacity to ensure reliable operation of the fuel oil fuelled machinery, are to be fitted, and arranged so that they can be operated in parallel to address the removal of gross contamination of water and abrasives.

2.5.5.2.2 The performance of the separator is not to be impaired by any equipment upstream or downstream of it in the system as recommended by the separator manufactures.

2.5.5.3 Equipment interfaces

2.5.5.3.1 Centrifugal separators are to be located to avoid oil spray or oil leakages onto hot surfaces or other sources of ignition, or onto rotating machinery parts. Where necessary, shielding is to be provided.

2.5.5.3.2 Centrifugal separators are to be located to allow easy access for routine maintenance.

2.5.5.4 Equipment Operations

2.5.5.4.1 The design and construction of centrifugal separators is to facilitate their maintenance in a safe manner.

2.5.5.5 Verification requirements

2.5.5.5.1 Approval

.1 Centrifugal separators are to be certified for a flow rating in accordance with a recognised standard, e.g. CEN Workshop Agreement (CWA) 15375 (latest revision).

.2 Centrifugal separators are to meet the safety requirements of a recognized standard, e.g. EN 12547, Centrifuges — Common safety requirements.

2.5.5.5.2 Factory acceptance testing

.1 Final testing of centrifugal separators is to be conducted in the presence of a surveyor. As an alternative, separators may be manufactured and tested under an Alternative Certification Scheme, see *Pt.1 Ch.1, Sec 4 of Rules and Regulations for the Construction and Classification of Steel Ships*.

2.5.5.5.3 Shipboard verification

.1 Verification of correct operation of centrifugal separators is to be conducted after installation on-board.

.2 Maintenance records of centrifugal separators are to be made available to Surveyors during regular surveys.

Section 3

Test Procedures to confirm the ability of RMF fuel oil pumps operation with marine fuels with low viscosity

3.1 Application

3.1.1 The following requirements are to be applied to the fuel oil pumps used in the fuel oil treatment and transfer systems when operating in Emissions Control Areas.

3.1.2 The requirements are applied to:

- Primary essential services fuel oil pumps (main and stand-by) used in all services that need to be maintained in continuous operation. These include: separator fuel oil supply pumps; booster pumps, feeder pumps, fuel valve cooling pumps, (in systems which use fuel oil for this service).
- Fuel pumps that are not required to be in continuous operation, e.g. fuel oil transfer pumps.

3.2 Fuel oil pump arrangements

3.2.1 For ships intending to use RMF and/or DMF in non-restricted areas and marine fuels with a sulphur content not exceeding 0.10 % m/m and minimum viscosity of 2 cSt in emission control areas, the pump arrangements are to be according to MSC.1/Circ.1467 in compliance with SOLAS regulation II-1/26.3.4. (See also *Pt.4, Ch.3, 4.10.4 of Rules and Regulations for the Construction and Classification of Steel Ships*).

3.3 Tests procedures to confirm the ability of HFO fuel oil pumps operation with marine fuels with a sulphur content of 0.10% and a minimum viscosity of 2,0 cSt

3.3.1 Type testing

3.3.1.1 Each type of fuel oil pump intended for use in a fuel oil system on board a ship is to be subjected to type testing.

3.3.1.2 Tests carried out for a particular type of pump will be accepted for all pumps of the same type built by both Licensors and Licensees.

3.3.2 Running test

3.3.2.1 A running test is to be carried out with a minimum or lower viscosity fuel oil with a sulphur content of 0.10 % m/m or less specified in ISO 8217 (latest edition) Specifications for Marine Fuels; recommended fuel oil viscosity value for the test should be 2 cSt at the fuel pump.

3.3.2.2 The lubricity of fuel oil for running test is to be less than 520 μm as determined by a high-frequency reciprocating rig test according to ISO 12156-1.

3.3.2.3 The running test is to be conducted for a minimum of 250 hours for pumps for both continuous and non-continuous operation and at a discharge pressure equal to the nominal pump pressure rating.

3.3.2.4 During the running test the following data is to be verified:

- a) volume rate of flow Q [m^3/h]
- b) delivery head H [m]
- c) pump power input P [kW]
- d) speed of rotation n [min^{-1}]

3.3.2.5 During the running test, the pump is to be checked for smooth running (for example VDI Regulation 2056 “Criteria for the assessment vibration in machines” could be used as a basis for acceptance) and bearing temperature. The assessment is to be based on a recognized international standard. This may be based on the pump manufacturer’s in-house testing procedures in agreement with IRS.

3.3.3 Pumps suitability

3.3.3.1 All elastomeric components in the fuel oil system (e.g. diaphragms) are to be made of fluoro-rubber or other material suitable for use with marine fuels according to MSC.1/Circ.1321.

3.3.3.2 Displacement pumps are to be fitted with relief valves. The discharge from the relief valve is normally to be led back to suction side of the pump.

3.3.3.3 The maximum amount of catalyst fines reaching the engine is to be 10 ppm Al+Si and in some instances this might rise to 15 ppm however every attempt must be made to reduce the catalyst to the lowest possible levels.

Note: Particle size has a significant influence on the capacity of the centrifugal separators to lower the level of catalyst fines in the fuel, with particles of 2 microns or less being particularly difficult to remove. The presence of particles of 2 microns size or lower may cause difficulties in achieving the 10 ppm limit. Engine manufacturer recommendations is also to be referred to for any further system specific recommendations.

3.3.3.4 Dedicated continuous monitoring of the quantity of catfines between the pump and the service tank outlet is to be considered. If continuous monitoring of catfines is not implemented, and the fuel type used is RMF, then weekly sampling and analysing of catfine level at service tank outlet is recommended to ensure that catfine level doesn't exceed maximum level.

3.3.3.5 Compatibility test kits, approved or recommended by the fuel oil manufacturer, is to be used when bunkering two or more different fuel types, e.g. a high sulphur and low 0.10 % m/m sulphur fuel.

3.3.3.6 An automated fuel oil changeover valve/system or manual valve/system that can provide for timed changeover of fuel oil from one type to another is to be provided and done in accordance with the engine manufacturers' recommendation.

3.3.3.7 Each vessel or installation is to have established procedures for fuel oil changeover and crew is to be trained on doing it safely.

3.3.4 Verification requirements for pump design and test documentation

3.3.4.1 All types of fuel oil pumps used for operation with low-sulphur fuel oil installed onboard are to be tested and the evidence of test is to be kept onboard.

3.3.4.2 The scope of design documentation supplied by the pump manufacturer and kept on board is to include:

- a) Pump(s) arrangement drawing, pump installation diagram with position and characteristics of sensors/monitoring system details,
- b) List of components with characteristics of materials critical for reliable operation of pump,
- c) Sealing arrangements,
- d) Reliability and life cycle data,
- e) Operational manual with performance and life cycle guidance,
- f) Test programme of the pump(s) for class survey.

3.3.4.3 The following certificates are required to be submitted and attached to the pump documentation:

3.3.4.3.1 The running test certificate containing:

- a) Manufacturer details,
- b) The test stand location and accreditation – approval details,
- c) Pump type and serial number,
- d) Duration of test,
- e) Viscosity of used medium,
- f) Parameters as mentioned in 3.3.2,
- g) Minimum operating temperature,
- h) Result of running test,

3.3.4.3.2 Hydraulic test certificate.

3.3.4.3.3 Materials certificates.